



Request for Council Action

TO: Mayor and City Council
THROUGH: Tim Murray, City Administrator
FROM: Travis Block, Public Works Director
MEETING DATE: October 23, 2018
SUBJECT: Approve Storm Sewer Repair Quote

Background:

A storm sewer structure has failed at the intersection of Willow St. and Tower Pl. and needs to be repaired. Staff does not have the equipment needed to make the repairs and has obtained two quotes for the repair of the structure. Results of the quotes are as follows:

| | |
|---------------------------------------|------------|
| BCM Grading-Excavating, Faribault, MN | \$8,920.00 |
| Heselton Construction, Faribault, MN | \$9,970.00 |

Funding will come from the Storm Sewer Fund (603). It is anticipated that the repair will be complete by November 30, 2018.

Recommendation:

Accept Storm Sewer Repair Quote from BCM Grading-Excavating of Faribault, MN

Attachments:

- Quotes



To: City of Faribault
Attn: Mike Glende

From: Andy Louis

Date: 10/18/18

Re: Bid for removing and replacing 48" CBMH at Willow Street and Tower Place

Scope of work includes the following

Mobilization
Remove existing structure
Furnish and install new 48" CBMH
Re-install existing casting

Total: \$8,920.00

Notes

1. All sawcutting, bituminous and curb removal, curb replacement, street replacement, sod or seed by others.



P.O. BOX 246
 680 NW 24TH STREET
 FARIBAULT, MN. 55021
 PHONE: 507-334-3901
 FAX: 507-334-0114

Job Code M8-158 Faribault Storm Repair Willow and Tower PL
 Job Description FARIBAULT - WILLOW STREET AND TOWER PLACE STORM MH REPAIR (REVISED 10-18-18)
 Job Location Intersection Willow St & Tower Place
 Job City Faribault
 Job County Rice
 Job State MN
 Bid Date 18-Oct-2018

| Line No. | Description | Proposal | Quantity | Unit of Measure | Unit Price | Total Price |
|-----------------------|---|----------|----------|-----------------|------------|-------------|
| | Subtotal Description | | | | | |
| 1 | MOBILIZATION | | 1.00 | LS | 650.00 | 650.00 |
| 5 | REMOVE CATCHBASIN | | 1.00 | EA | 155.00 | 155.00 |
| 6 | 72" DIAMETER CATCHBASIN MANHOLE @6.6' BUILD | | 1.00 | EA | 6,610.00 | 6,610.00 |
| 7 | R3067V CASTING | | 1.00 | EA | 565.00 | 565.00 |
| 8 | 24" RCP | | 8.00 | LF | 58.00 | 464.00 |
| 9 | 12" RCP (4 EA STUBS) W/CONSTRUCTION JOINTS | | 32.00 | LF | 37.00 | 1,184.00 |
| 7 | 12" Class 5 | | 18.00 | TN | 19.00 | 342.00 |
| Subtotal: | | | | | | 9,970.00 |
| Running Total: | | | | | | 9,970.00 |
| GRAND TOTAL: | | | | | | 9,970.00 |

Proposal Certification

Submitted By: Hesellon Construction, LLC
 P.O. Box 246
 680 NW 24th St.
 Faribault, MN. 55021
 Cell No. 507-696-7345
 507-334-3901

Signed: Dean Hammer
 Title: Estimator
 Date: 10/18/18